

ESTIMATE FOR:

My Client
 Your Street
 New Orleans, Louisiana 70116

DATE: 02/07/2020**FROM:**

SBI, Inc.
 187 Thoroughbred Avenue
 LAPLACE, LA 70068
 Office: 504.382.2410

LA State Commercial Building Construction (statewide) # 58032
 LA State Residential Contractor (statewide) # 885905
 LA State Electrical License (statewide) # 58032
 LA State Mechanical License (statewide) # 58032

Reason: Roof Evaluation**Installation of "Vermont" Slate Tiled Roof**

Stage job with 20-yard dumpster
 Remove existing hip tile – stack for reuse
 Remove existing roof. (8 squares) (800 square feet)
 Supply and install 5/8" CDX plywood roof decking.
 Supply and install all roof jacks and flashing and flanges.
 Supply and install 30 lbs. U.L. saturated felt paper underlayment
 Install Duro-last (PVC) membrane at roof system with rain drainage scuppers, terminations and seams.
 Install termination bar and welded heat seams where slate won't be installed due to low slope.
 Fabricate and install copper flashing for shed roof and to meet Historic District requirements.
 Supply and install new Vermont Slate roof using copper nails
 Slate to be standard unfaded gray/green sized 10" wide x 18" length 1/4" – 3/8" thick rough texture
 "A light Gray-Green Slate with some clouded grayer/black markings". Produced in Vermont
 Install existing saved and stacked hip tiles
 Perform a clean sweep of entire job site removing any nails and debris

TOTAL INVESTMENT**\$9,600**