

BID OPTION #1
N1012 3.5 Mile To'Nanees'Dizi Road Improvements
BID# 22-01-2691LE
Navajo Division of Transportation
December 28, 2021

FP 14 Spec	Description	Quantity	Unit Price	Bid Amount	Bid Amount in Writing
Section 151	Mobilization	1	LS		
Section 152	Construction Staking and Surveying	1	LS		
Section 154	Contractor Sampling and Testing	1	LS		
Section 635	Temporary Traffic Control	1	LS		
Section 212	Grading/Shaping Subgrade/Side Ditches to Typical Road Section	3.5	MILE		
Section 311	Place Aggregate Base Course, 4" Depth, Grading D FP-14(Minus Options #1 & #2)	8,440	TON		
Section 311	Bid Option #1: Place 6" Minus Gravel @ Sta 182+00 to Sta 188+00 (Underground Spring Area) See Details in Plans	1,563	TON		
Section 725.02	Apply Chemical Stabilizer to Finished Compacted Aggregate Base Course Surface (Calcium Chloride or Magnesium Chloride or Equivalent)	41,066	SY		
Subtotal					
Navajo Nation Tax 6%					
Total Bid					

COMPACTION WATER IS INCIDENTAL TO EACH BID ITEM. CONTRACTOR MUST SECURE WATER SOURCE FROM NAVAJO NATION WATER RESOURCES MANAGEMENT.

Signature of Firm's Authorizing Person

Firm Name: _____

Firm Address: _____

Firm Contact Information: _____