



**BID SCHEDULE
NAVAJO NATION DIVISION OF TRANSPORTATION**

PROJECT: US 491 Chee Dodge Elementary School Access Improvements

Date: March 8, 2023

LENGTH: 0.3 miles

NMDOT ITEM #	DESCRIPTION	Quantity	Units	Unit Bid Price	Total Price
201000	CLEARING AND GRUBBING	1	LPSM	\$ -	\$ -
203000	UNCLASSIFIED EXCAVATION	4,200	CUYD	\$ -	\$ -
207000	SUBGRADE PREPARATION	4,400	SQYD	\$ -	\$ -
303000	BASE COURSE	2,840	TON	\$ -	\$ -
407000	ASPHALT MATERIAL FOR TACK COAT	2	TON	\$ -	\$ -
408100	PRIME COAT MATERIAL	9	TON	\$ -	\$ -
416106	MINOR PAVING TYPE I, HMA SP-III	4,600	SQYD	\$ -	\$ -
601000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1	LPSM	\$ -	\$ -
601110	REMOVAL OF SURFACING	410	SQYD	\$ -	\$ -
603281	SWPPP PLAN PREPARATION AND MAINTENANCE	1	LPSM	\$ -	\$ -
609324	CONCRETE SLOPED CURB & GUTTER 6" X 24"	1,820	LNFT	\$ -	\$ -
618000	TRAFFIC CONTROL MANAGEMENT	1	LPSM	\$ -	\$ -
621000	MOBILIZATION	1	LPSM	\$ -	\$ -
667210	LANDSCAPE GRAVEL	1,200	SQYD	\$ -	\$ -
701000	PANEL SIGNS	130	SQFT	\$ -	\$ -
701100	STEEL POST AND BASE POST FOR ALUMNINUM PANEL SIGNS	80	LNFT	\$ -	\$ -
702810	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	1	LPSM	\$ -	\$ -
703001	OBJECT MARKER TYPE 1	2	EACH	\$ -	\$ -
703004	OBJECT MARKER TYPE 2	2	EACH	\$ -	\$ -
704000	RETROREFLECTORIZED PAINTED MARKINGS 4"	8,700	LNFT	\$ -	\$ -
704704	HOT THEMROPLASTIC PAVEMENT MARKINGS, 24"	30	LNFT	\$ -	\$ -
704717	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	2	EACH	\$ -	\$ -
704720	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	1	EACH	\$ -	\$ -
704735	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	4	EACH	\$ -	\$ -
715003	RECTANGULAR RAPID-FLASHING BEACON	1	EACH	\$ -	\$ -
801000	CONSTRUCTION STAKING BY THE CONTRACTOR	1	LPSM	\$ -	\$ -
802000	POST CONSTRUCTION PLANS	1	LPSM	\$ -	\$ -
				Subtotal:	\$ -
				Navajo Nation Tax (6%):	\$ -
				Total Bid Price:	\$ -

Contractor Name

SCOPE-OF-WORK

The proposed work consists of furnishing all labor, material, equipment and incidentals necessary for construction of 0.3 miles of roadway widening including the addition of shoulders and acceleration and deceleration lanes, concrete median improvements including the addition of landscape gravel, sloped curb and gutter construction in the median, installation of signs, striping and other miscellaneous work as called for in the design plans and specifications for this project. The quantities listed for each item is estimated and the Unit Price is applicable to each as given in the Bid Schedule above. The final pay quantity measurements shall be rounded to the significant figures given in this bid schedule for the final pay estimate. Payment for work performed on Items furnished will be made in accordance with Sub-Section 109.05, Scope of Payment of FP-14. **The Unit Bid Price must include all overhead, profit, and bonding.**