



**BID SCHEDULE
NAVAJO NATION DIVISION OF TRANSPORTATION**

PROJECT: N5-NM 371 Intersection Radius Project

Date: June 18, 2026

LENGTH: 0.059 miles

NMDOT ITEM #	DESCRIPTION	Quantity	Units	Unit Bid Price	Total Price
201000	CLEARING AND GRUBBING	LS	LS	\$	\$
203000	UNCLASSIFIED EXCAVATION	34	C.Y.	\$	\$
203100	BORROW	50	C.Y.	\$	\$
207000	SUBGRADE PREPARATION	370	S.Y.	\$	\$
303000	BASE COURSE	110	TON	\$	\$
408100	PRIME COAT MATERIAL	1	TON	\$	\$
416103	MINOR PAVING TYPE I, HMA SP-III	50	TON	\$	\$
601000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	LS	\$	\$
601110	REMOVAL OF SURFACING	140	S.Y.	\$	\$
607004	BARBED WIRE FENCE 4'	130	L.F.	\$	\$
610000	CATTLE GUARD	40	L.F.	\$	\$
618000	TRAFFIC CONTROL MANAGEMENT	LS	LS	\$	\$
621000	MOBILIZATION	LS	LS	\$	\$
701000	PANEL SIGNS	10	S.F.	\$	\$
701100	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	20	L.F.	\$	\$
702810	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	LS	LS	\$	\$
704000	RETROREFLECTORIZED PAINTED MARKINGS 4"	350	L.F.	\$	\$
704004	RETROREFLECTORIZED PAINTED MARKINGS 12"	130	L.F.	\$	\$
721000	REMOVAL OF PAVEMENT MARKING	60	L.F.	\$	\$
801000	CONSTRUCTION STAKING BY THE CONTRACTOR	LS	LS	\$	\$
802000	POST CONSTRUCTION PLANS	LS	LS	\$	\$
				Subtotal:	\$
				Navajo Nation Tax (6%):	\$
				Total Bid Price:	\$

Contractor Name

SCOPE-OF-WORK

The proposed work consists of furnishing all labor, material, equipment and incidentals necessary for the reconstruction of the northwest corner of the N5/NM 371 intersection. The quantities listed for each item is estimated and the Unit Price is applicable to each as given in the Bid Schedule above.