



**BID SCHEDULE  
NAVAJO NATION DIVISION OF TRANSPORTATION**

**PROJECT: N55(1-2)4**

**Date: July 17, 2025**

**LENGTH: 8.26 miles**

ITEM	DESCRIPTION	Quantity	Units	Unit Bid Price	Total Price
10901-0000	Extra & Miscellaneous Work - Authorized under Suppl. Spec. 109.02(s) of Exhibit F	All Required	Lump Sum	\$ 300,000.00	\$ 300,000.00
FP-14: 31002-1100	CONTINUOUS COLD IN PLACE RECYCLED ASPHALT BASE COURSE (CCRAC) 3", TYPE A	126,100	SY	\$ -	\$ -
410020	TWO COURSE SURFACE TREATMENT	126,100	SY	\$ -	\$ -
203200	UNSUITABLE MATERIAL EXCAVATION	1,900	CY	\$ -	\$ -
303000	BASE COURSE	875	TON	\$ -	\$ -
<del>407800</del>	<del>ASPHALT MATERIAL FOR TACK COAT</del>	<del>0</del>	<del>TON</del>	<del>\$ -</del>	<del>\$ -</del>
408100	PRIME COAT MATERIAL	242	TON	\$ -	\$ -
<del>411800</del>	<del>HOT POURED CRACK SEALING</del>	<del>0</del>	<del>MI</del>	<del>\$ -</del>	<del>\$ -</del>
<del>414801</del>	<del>COLD MILLING (ASPHALT)</del>	<del>0</del>	<del>SY</del>	<del>\$ -</del>	<del>\$ -</del>
<del>423283</del>	<del>HMA SP IV COMPLETE (2" OVERLAY)</del>	<del>0</del>	<del>TON</del>	<del>\$ -</del>	<del>\$ -</del>
423283	HMA SP IV COMPLETE (3" LIFT)	420	TON	\$ -	\$ -
<del>407801</del>	<del>FOG SEAL</del>	<del>0</del>	<del>TON</del>	<del>\$ -</del>	<del>\$ -</del>
601100	REMOVAL OF SURFACING	1	LS	\$ -	\$ -
604300	GEOGRID REINFORCEMENT	3,200	SY	\$ -	\$ -
618000	TRAFFIC CONTROL MANAGEMENT	1	LS	\$ -	\$ -
621000	MOBILIZATION	1	LS	\$ -	\$ -
702810	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	1	LS	\$ -	\$ -
704000	RETROFLECTORIZED PAVEMENT MARKINGS 4"	98,200	LF	\$ -	\$ -
801000	CONSTRUCTION STAKING BY THE CONTRACTOR	1	LS	\$ -	\$ -
				Subtotal:	\$300,000.00
				Tax (6.25%):	\$18,750.00
				<b>Total Bid Price:</b>	<b>\$318,750.00</b>

**Contractor Name**

**SCOPE-OF-WORK**

The proposed work consists of furnishing all labor, material, equipment and incidentals necessary for construction of 8.26 miles of roadway excavation; placement of aggregate base course, geogrid and asphalt pavement; continuous cold recycled asphalt course pavement of the existing pavement surface; two course surface treatment/chip seal, striping, and other miscellaneous construction in accordance with the specification and design drawings for this Project. The quantities listed for each item is estimated and the Unit Price is applicable to each as given in the Bid Schedule above. The final pay quantity measurements shall be rounded to the significant figures given in this bid schedule for the final pay estimate. Payment for work performed on Items furnished will be made in accordance with Sub-Section 109.05, Scope of Payment of FP-14. **The Unit Bid Price must include all overhead, profit, and bonding.**