

ADDENDUM #2
CONSTRUCTION SPECIFICATIONS AND CONTRACT DOCUMENTS
N9402 Road Project
RFP-BID #25-10-3901DB

Navajo Division of Transportation
P.O. Box 4620
Window Rock, Arizona 86515

April 21, 2026

The following revisions to the specifications and drawings shall become a part of the above-referenced contract documents.

1. ADD CONTRACT REQUIRMENT:

- No additional Contract Requirements and/or Revisions are required.

2. The following questions were submitted prior to the deadline in the RFP and the following responses are provided:

- a. 20304-1000 calls for the demo of structure and obstructions. The only demo I can find in the plans is for culvert and fences however the culvert demo is accounted for in 60701-1000 can I assume that the first line item refers to the fencing?
 - i. Yes, the 20304-1000 bid item covers the fence and cattle guard removal efforts. It also covers the removal of any other obstructions that are within the project limits. Please note that the existing fence materials should be offered to the property owners before removing it from the property.
- b. 20401-000 is for roadway excavation, but most of the cross sections in the plans call for a fill. Should we assume that the CYds it this line item stay on site?
 - i. The EARTHWORK SUMMARY quantity table is located on sheet 7 of the Wilson plans. The noted fill in the cross sections necessary to build the

roadway prism is shown in the EMBANKMENT column of this table. The material and effort to construct this fill shall come from and be included in the ROADWAY EXCAVATION bid item unit price. All material that is excavated on the project should be utilized to build up the fill sections in the cross sections.

- c. 61601-1000 calls for slope paving concrete. We cannot find any reference to this in the plans. Can you please explain what this is?
 - i. The 61601-1000 Slope Paving Concrete bid item work is located at structure DS-17 (STA 304+80). Please refer to sheets 1, 11 and 22 of 33 of the Dibble plans for details on the construction.

END OF ADDENDUM #2